

QOUTATION FOR AB BLOCK EXTENSION AND RENNOVATION WORKS AT U.C.COLLEGE					
ALUVA					
Sl.No	Specification	Unit	Quantity	Rate	Amount
1	R.C.C. 1:2:4 mix using 20 mm broken stone including all forms of reinforcement works, scaffolding, centering, shuttering, watering, curing etc for column, lintel, beam, sunshade, roof slab, stair etc. complete				
	F.FLOOR	m3	23.00		
2	Solid block masonry in cm 1:6 using 30x20x15cm and 30X10X15 including scaffolding, watering, curing for walls, parapet, stair etc.				
	G.FLR(20cm thk wall)	m3	39.09		
	G.FLR(100cm thk wall)	m3	3.17		
	F.FLOOR(20cm thk wall)	m3	81.65		
3	Aerocon block masonry in CM 1:6 using 60x20x20 including scaffolding, watering, curing etc for walls				
	F.FLOOR(20cm thk wall)	m3	21.6		
4	Suppling and fixing glazed windows and ventilators with cheru Teak wood frames and 4mm thick glass shutters of std.design including all necessary fittings.				
	F.FLOOR	m2	32.70		
5	Supplying and fixing hard wood pannelled door shutter				
	F.FLOOR	m2	13.00		
6	Plastering with CM 1:4, 12mm thk. One coat floated to the walls including scaffolding, watering, curing etc. complete				
	G.FLOOR	m2	270.40		
	F.FLOOR	m2	823.75		
7	Plastering to the under side of slabs & sunshades at all levels with C.M 1:3, 9 mm thick including charges for chipping & making the entire surface rough for plastering.				
	G.FLOOR	m2	45.00		
	F.FLOOR	m2	6.64		

8	Floor finishing with vitrified tiles over a base coat of cm 1:3 and cement grout including watering,curing and pointing with coloured cement etc complete				
	G.FLOOR	m2	24.80		
	F.FLOOR	m2	445.00		
9	Skirting wall side with vitrified tile over a base coat of C.M. 1:3 and coloured cement grout including watering, ect complete				
	G.FLOOR	Rm	190.00		
	F.FLOOR	Rm	190.00		
10	Supplying, fabricating and laying earthen tiles over steel truss, using GI rectangular sections, with all neccessary fittings, including cost of all materials and labour but excluding cost of tiles.				
	F.FLOOR	m2	872.00		
11	Painting with two coats of emulsion coat over the plasterd area and ceiling after priming coat (2 coat)including rubbing ,curing ,watering etc. complete				
	G.FLOOR & F.FLOOR	m2	1300.00		
12	Painting & polishing doors,windows,ventilators etc. with synthetic enamel painting two coats over abase coat of wood or metal primer including rubbing , cleaning etc.				
	G.FLOOR	m2	60.00		
13	Providing false roof using gypsum ceiling for auditorium	m2	185.00		
14	Providing HVAC system in auditorium and sophiscated instrumentation lab	LS			
15	Providing watersupply and sanitary arrangements including, construction of septic tank, soak pit, inspection chamber,P.V.C. over head water tank, manhole etc. complete.	LS			
16	Electrification arrangements including I.S.I. mark conceled wiring and all other necessary fittings.	LS			
				Total Rs	

Terms & Conditions

- 1) Cement : Ultratech, ACC, Malabar
- 2) Steel : Vizag, SAIL Fe 500 and above
- 3) Tile : Vitrified tiles of brand Kajaria (Rate range 50.00-60.00/sft)
- 4) Paint: Asian Paints (Exterior & Interior Wall Primer, Ultima weather coat, Apcolite interior emulsion)
- 5) GI rectangular sections for roof work should be of brand appollo and 16 gauge pipes.
- 6) Electrical Switches and boxes- Legrand, Wires - Finolex
- 7) Plumbing pipes-(ISI standard pipes and fittings), Sanitary Fittings- Cera/Hindware
- 8) Electricity and Water will be provided at the site.
- 9) All rates should include cost of all materials and labour.
- 10) Work bills will be prepared after taking actual measurements from the site.
- 11) Rate of works outside the quotation will be approved only after negotiations.
- 12) All materials to be used in the site must need prior approval from the project engineer.